

 <p style="text-align: center;">State of Ohio Weatherization Program Standards</p>	Section	<b>MOBILE HOME FINAL INSPECTION</b>
	Subject	<b>Overall Building Shell</b>

*VERIFICATION 802-1.1*

Ensure that any additions have been documented and inspected.

**additions**  
802-1.1a

Ensure that fire escape windows have not been sealed shut. Ensure that jalousie windows operate correctly, or have clips added if they do not.

**windows**  
802-1.1b

Ensure that prime doors are present and operate correctly.

**doors**  
802-1.1c

Ensure that drainage problems, if any, have been corrected or documented.

**drainage**  
802-1.1d

Ensure that a continuous ground vapor barrier is in place if there is existing draftproofing.

**vapor barrier**  
802-1.1e

Ensure that combustion air intake is operational and not obstructed.

**combustion air intake**  
802-1.1f

Perform a final blower door test (see 1506-1) and compare it with the results of the Building Tightness Limits calculation. Decide if additional ventilation equipment needs to be installed to assure safe indoor air quality. Ensure that the target reduction goal has been met or surpassed. Verify the valid technical reasons that prevented the goal from being achieved, and ensure that they are documented and placed in the client file.

**blower door test**  
802-1.1g

Ensure that a distribution system leakage test is performed and that the results are acceptable.

**Distribution System  
Leakage Test**  
802-1.1h

Ensure that the BTL minimum level of air leakage is available within the home.

**target reduction**  
802-1.1i